ANCHOR USER MANUAL SAFETYLINK EQUIPMENT SELECTION, USE AND MAINTENANCE

TO BE READ IN CONJUNCTION WITH SITE SPECIFIC INFORMATION

٩

Safety*Link* is an innovative anchor company achieving success and keeping you safe whilst working at heights.

- ROOF ANCHORS
- HORIZONTAL LIFELINES
- S PERMANENT LADDERS
- LADDER STABILISERS
- **TEMPORARY ANCHOR**
- **N** WALKWAY & GUARDRAIL
- X-RAIL HORIZONTAL RAIL





Read entire handbook before installing SafetyLink products. All products must be installed in accordance with SafetyLink's installation handbook, using only products supplied by SafetyLink Pty Ltd. Failure to follow all warnings and instructions may result in a serious injury or death.



Asia-Pacific/The Americas info@safetylink.com Europe/Africa/Middle East europe.sales@safetylink.com Northern Europe uk.sales@safetylink.com

www.safetylink.com

TABLE OF CONTENTS

SCOPE
LEGISLATION4
RISK ASSESSMENT AND FALL PREVENTION5
RISK ASSESSMENT:5
STEPS TO COMPLETE A RISK ASSESSMENT ON A PARTICULAR JOB:
CONTROL MEASURES FOR FALL PREVENTION:5
USE OF SAFETYLINK SYSTEM6
USAGE INFORMATION6
EQUIPMENT COMBINATION6
SHARP EDGES6
LATERAL SWING (THE PENDULUM EFFECT)6
USE OF SAFETYLINK SYSTEM
FALL-ARREST AND FALL RESTRAINT7
USE OF SAFETYLINK SYSTEM8
OBJECTS FALLING FROM HEIGHTS8
ELECTRICAL HAZARDS8
USER COMPETENCY8
NUMBER OF USERS
SYSTEM INFORMATION PLATES LABELS AND SIGNS8
FIXED LADDERLINK – LADDER SUPPORT BRACKETS
INSTALLATION FOR METAL ROOFS – UNDER ROOF SHEETING
INSTALLATION FOR METAL ROOFS – ON TOP OF ROOF SHEETING
INSTALLATION FOR TILED ROOFS
FIXED LADDERLINK – WALL MOUNTED LADDER SUPPORT BRACKET
FIXED LADDERLINK – PARAPET MOUNTED LADDER SUPPORT BRACKET
SAFETYLINK ANCHORAGES – PROGRESSING ALONG SYSTEM – FIGURE 3
SAFETYLINK ANCHORAGES16
PROGRESSING ALONG THE ANCHOR SYSTEM16
DISCONNECTING FROM THE ANCHOR SYSTEM16
MAINTENANCE
ANCHORS AND LADDER STABILISERS
INSTALLATION AND RECERTIFICATION CHECKLIST18
10 YEAR RECERTIFICATION POLICY
EXPERT FALL PROTECTION PLANNING
NOTES
IN CASE OF ACCIDENT





▲ WARNINGS:

This supplement is a guide only and is not intended to substitute training courses in height safety and product installation.

Legislative requirements vary according to the region you live in please visit the appropriate workcover website for further information.

Individual situations vary considerably therefore you should seek appropriate legal advice if you need assistance on the application of law to your situation.

The **PURPOSE** of this supplement is:

- to outline the selection process of a SafetyLink System.
- to provide information about the safe use of the SafetyLink Systems.
- to make users aware of maintenance requirements of their SafetyLink System.
- to provide users with information about possible issues that may need to be addressed with a SafetyLink Height Safety System.





▲ WARNINGS:

Legislative requirements vary according to the region you live in please visit the appropriate website for further information.

AUSTRALIA

SafeWork NSW (New South Wales) P: 13 10 50	W:	www.safework.nsw.gov.au
WorkSafe Victoria P: 1800 136 089	W:	www.worksafe.vic.gov.au
WorkCover Queensland P: 1300 362 128	W:	www.worksafe.qld.gov.au
SafeWork SA (South Australia) P: 1300 365 255	W:	www.safework.sa.gov.au
WorkSafe Tasmania P: 1300 366 322	W:	www.worksafe.tas.gov.au
Worksafe Western Australia P: 1300 307 877	W:	www.commerce.wa.gov.au/worksafe/
NT Worksafe (Northern Territory) P: 1800 019 115	W:	www.worksafe.nt.gov.au
WorkSafe (Australian Capital Territory) P: 13 22 81	W:	http://www.worksafe.act.gov.au/
NEW ZEALAND		
WorkSafe (New Zealand) P: 0800 030 040	W:	www.worksafe.govt.nz/worksafe/

LEGISLATION:

- For legislative requirements contact the appropriate authority for your state.
- Specific height safety requirements exist under legislation, regulations and codes of practice for each state.
- The fundamental principle throughout is that employers and self employed persons must **provide a safe working environment** to maintain the health, safety and welfare of employees and other persons exposed to that working environment.
- Employees also have an obligation to take reasonable steps to protect their own health, safety and welfare and others in their working environment. If you need help to meet these obligations contact the appropriate authority for your state.





RISK ASSESSMENT:

- Risk assessments should be conducted in consultation with workers for all work conducted irrespective of height, using the appropriate measures of control.
- All fall arrest systems and lifeline systems require a risk assessment prior to use.
- A fall rescue plan should also be developed prior to use.
- Workers using a fall arrest system or lifeline system should never work alone.

STEPS TO COMPLETE A RISK ASSESSMENT ON A PARTICULAR JOB:

- 1. Identify the hazards.
- 2. Assess the hazard determining how great the risk is, the likelihood and consequence of each hazard.
- 3. Make decisions on what can be done to control the risk, in order of the following:
 - Elimination (Eliminate the need to access the fall risk area).
 - Substitution (Provide alternative methods to access the point or item which avoids the risk of a fall for example a walkway).
 - Isolation (enclose fall risk area so that is cannot be reached).
 - Fall protection (provide personal protective equipment which either prevents a fall or reduces the risk or severity of a fall).
- 4. Implement a review process to reassess control measures and consider whether they are still appropriately controlling the risk.

CONTROL MEASURES FOR FALL PREVENTION:

While undertaking a risk assessment where there is risk associated with working at heights the following controls need to be implemented in order of hierarchy:

- 1. Provision and maintenance of a stable and secure fenced work platform, that is scaffolding equipment or other temporary work platform. If this is not practicable then;
- 2. Provision and maintenance of secure perimeter screen, fencing or handrails capable of preventing a fall from heights. If this is not practicable then;
- 3. Provision of other forms of physical restraint that are capable of arresting a fall.

It is important to be aware that there are risks associated with working at any elevated position. Therefore, there are no minimum requirements for implementation of the above hierarchy of control.

In determining the control measures to be implemented for fall prevention an employer is only allowed to use restraints or fall arrest devices where it is not reasonably practical to use scaffold or guardrail systems. Where restraint or fall arrest devices have been implemented documentation needs to be produced showing reasons why it was not practical to use scaffolding or guardrails.





▲ WARNINGS & HAZARDS

During installation you must be safe at all times.

Persons working at heights should not work alone. A person suspended mid air following a fall can suffer serious injury or death if a rescue is not implemented as quickly as possible.

- SafetyLink[™] Systems are to be used only by people with necessary competence and training.
- When the SafetyLink[™] System is exposed to a corrosive or extreme environment which could significantly reduce the working load of the SafetyLink[™] System, the manufacturer or a competent height safety installer shall be consulted prior to such exposure.
- The building or structure for the anchorages should be assessed by an engineer, unless it is clear to a competent height safety installer that the structure is adequate.
- All safety procedures must be complied with in accordance with the current safety code(s) of practice(s) for working at heights. Ensure safety at all times by being attached to suitable anchor points and approved safety equipment or approved scaffolding.
- Inspect all personal protection equipment and attachment points for defects and damage.
- Ensure any equipment that needs to be out of service or isolated before accessing height safety equipment is done so.
- Ensure weather conditions are suitable for usage of the height safety equipment.

USAGE INFORMATION

Users should assure themselves immediately before and after use that the systems is in good order and condition and has been inspected, serviced where required and maintained in accordance with the manufacturer's instructions (see maintenance section of this manual).

Users should ensure that all the equipment is in good condition and working order before attempting to use the system. In particular clothing becoming caught up in SafeLink[™] Shuttle preventing proper use of system.

If the user is carrying tools they must be secured to ensure they do not obstruct the users' movement along the system.

EQUIPMENT COMBINATION

For Lifeline system users must connect to the system using only SafeLink[™] Shuttle and originally supplied Karabiner only. Substitution of originally supplied equipment may impede the use of the equipment. Users should consult a SafetyLink[™] authorised personal if they have any questions in regard to combining equipment and suitability.

SHARP EDGES

If the possibility of a fall exists near a sharp edge which could result in weakening on a lanyard or anchorage line, protective covering should be placed over the sharp edge to diminish the damage during a fall.

LATERAL SWING (THE PENDULUM EFFECT)

Anchorages: This situation occurs where there is a lateral offset between the line from the anchorage point to the operator and the line or direction of potential fall, in the event of a fall the operator may suffer hazardous lateral swing. (see below illustrations). To eliminate the pendulum attention needs to be made to the positioning of single anchors, or the use of diversion anchors.






USE OF SAFETYLINK SYSTEM


FALL-ARREST AND FALL RESTRAINT



User always in total restraint: No chance to fall.



Limited free fall: Free fall distance limited to less than 600 mm.



Free fall: Freefall distance greater than 600 mm.



OBJECTS FALLING FROM HEIGHTS

SafetyLink Systems safeguard people from falling from heights but do not prevent objects falling from heights. Additional controls need to be implemented to prevent injury from objects falling from heights.

ELECTRICAL HAZARDS

Major risks are associated with working in close proximity to overhead electrical powerlines. Specific control measures need to be followed in accordance with your states legislation, regulation and codes of practices.

USER COMPETENCY

All users of SafetyLink system must be fully trained and competent in the correct use of this product prior to being allowed to use the system.

They should have a full understanding of all Manufacturer's instructions on all equipment used on this system.

It is the responsibility of the user and purchaser of this equipment to ensure all people accessing the equipment are fully trained.

Training should be repeated periodically.

NUMBER OF USERS

See system information and labelling for Maximum users.

SYSTEM INFORMATION PLATES LABELS AND SIGNS

System information plate must be displayed on each regular entry point. The information plate will contain the following information:

- Manufacturer's and installer's name and installation date.
- System number.
- Servicing requirements and instructions, together with servicing intervals.

Example:

WA	Rľ	NII	NG 1			CESS Australia 1300 789 545 International +61 249 641068 www.safetylink.com
THIS SYSTEM MUST: • BE USED ONLY BY C • BE USED BY PERSON • HAVE ALL SAFETY PI THE CURRENT CODE • BE USED WITH AF • BE CLOSED IMMEDID: • BE CLOSED IMMEDID: • DCHEMICALS. REC • BE INSPECTED EVEN	NS WITH ROCEDUE S OF PR DEROPRIA TELY IN PEN UPC	RELEVAN RES COMP ACTICE FO HARNESS ATE LEGIS THE EVEN DN REPAIR	AUTHORISATION ON PLIED WITH AS STATE DR WORKING AT HEIG WITH ENERGY ABSC LATION, REGULATION T OF A FALL, DAMAGI & RE-CERTIFICATION	D IN BHTS. DRBER NS AND E OR E	STANDARD	ANCHOR POINTS - QTY
month/	20	year	month/	20	year	LOAD RATING kN
month/	20	year	month/	20	year	NO. OF PERSONS PER ANCHOR
month/	20	year	month/	20	year	SYSTEM IDENTIFICATION NO:
month/	20	year	month/	20	year	INSTALLED/CERTIFIED DATE:
month/		vear	month/		year	DUE SERVICE DATE:





FIXED LADDERLINK – LADDER SUPPORT BRACKETS



Product Code: LADFX001

Product Code: LADFX002


Product Code: LADFX003

All safety procedures must comply in accordance with the current safety code(s) of practice(s) for working at heights. Ensure safety at all times during and after installation by using an appropriate height safety protection system.

- ▲ Adjusting the pitch of the LadderLink to suit steeper roof pitches may be required. This must be completed with an appropriate sheet metal bending machine only. LadderLink's are made from high tensile aluminium, the bender must be set on a high radius to prevent cracking. Failure to do so may result in a damaged and unsafe ladder bracket.
- ▲ Always use a leash in conjunction with securing points on the LadderLink to secure your ladder once fitted to a ladder bracket.
- ${\rm \Delta}$ $\,$ Protective coating must not be removed.

Fixed LadderLink: Safe Ladder Access

Made from marine grade aluminium the LadderLink is designed to support a ladder, stopping sideways movement and therefore holding the ladder in place safely. In addition the LadderLink has securing points to tie off the ladder providing a safe access point.








FIXED LADDERLINK – METAL ROOF LADDER SUPPORT BRACKET

INSTALLATION FOR METAL ROOFS – UNDER ROOF SHEETING

- 1. To install the LadderLink simply remove existing hex head roofing screws along the bottom edge of the roof sheeting at the desired location.
- 2. Slide the ladder bracket under the roof sheeting between the sheeting and batten as shown in the diagram below.
- 3. Position the ladder bracket so the rolled section is centred over the gutters front edge.
- 4. Once the ladder bracket is in the desired location, re-install the hex head roofing screws through the original holes, through the ladder bracket and into the roof batten below.
- 5. Ensure that a minimum of three (3) x 12g 65mm roofing screws anchor the ladder bracket to the structure (recommended to pilot drill holes).








FIXED LADDERLINK – METAL ROOF LADDER SUPPORT BRACKET

INSTALLATION FOR METAL ROOFS - ON TOP OF ROOF SHEETING

- 1. To install the LadderLink simply remove existing hex head roofing screws along the bottom edge of the roof sheeting at the desired location.
- 2. Place the ladder bracket on top of the roof sheeting as shown in the diagram below.
- 3. Position the ladder bracket so the rolled section is centred over the gutters front edge.
- 4. Once the ladder bracket is in the desired location, re-install the hex head roofing screws through the ladder bracket, ensure the screws go through the roof sheeting and into the roof batten below.
- 5. Ensure that a minimum of three (3) x 12g 65mm roofing screws anchor the ladder bracket to the structure (recommended to pilot drill holes).
- 6. Install an additional two (2) x 8mm Rivets at the top corners 50mm down from the top edge, see below diagram. This must be completed to prevent rocking of the ladder bracket.








FIXED LADDERLINK – TILED ROOF LADDER SUPPORT BRACKET

INSTALLATION FOR TILED ROOFS

- 1. To install the LadderLink simply remove roof tiles at the desired location.
- 2. Place the ladder bracket onto the batten, ensure a rafter is centred below the ladder bracket.
- 3. Adjust the ladder bracket so the rolled section is centred over the gutter's front edge, as shown in the diagram below.
- 4. Once the ladder bracket is in the desired location, install three (3) x 65mm 12g hex head roofing screws through the ladder bracket and into the roof batten below (recommended to pilot drill holes).
- 5. Cut a short tile batten to fit as a spacer under the ladder bracket between the rafter and LadderLink.
- 6. Using one (1) x 100mm 14g hex head roofing screw, anchor the ladder bracket to the rafter below (recommended to pilot drill holes). This should be centred and installed 50mm down from the top edge of the ladder bracket (see below diagram).
- 7. Ensure that a minimum of three (3) x 12g 65mm and one (1) x 14g x 100mm roofing screws anchor the ladder bracket to the structure.
- 8. Ensure the timber structure is secured in accordance with current Building Codes.



FIXED LADDERLINK - WALL MOUNTED LADDER SUPPORT BRACKET

Wall Mounted - Product Code: LADFX003


- To install the LadderLink simply place in the desired location, ensuring there is suitable structure to support the brackets use.
- Once the ladder bracket is in the desired location, drill securing holes in both the LadderLink and mounting structure to suit method of attachment (see recommended fixing options below).
- Ensure that a minimum of four (4) appropriate fixings are used to anchor the ladder bracket to the structure.
- Fixings should be evenly spaced ideally 50mm in from the LadderLink edges to create a secure installation (see below diagram).

FIXING TO TIMBER WALL

- 1. Drill and install 4 (four) 14g x 75mm roofing screws (recommended to pilot drill holes).
- 2. Ensure the timber structure is secured in accordance with current Building Codes.

FIXING TO CONCRETE WALL

- 1. Drill and install 4 (four) M8 masonry bolts or equivalent anchor.
- 2. Ensure anchoring bolts are a minimum of 80mm from concrete wall edges.







Wall Mounted - Product Code: LADFX0010


- To install the LadderLink simply place in the desired location, ensuring there is suitable structure to support the brackets use.
- Once the ladder bracket is in the desired location, drill securing holes in both the LadderLink and mounting structure to suit method of attachment (see recommended fixing options below).
- Ensure that a minimum of four (4) appropriate fixings are used to anchor the ladder bracket to the structure.
- Fixings should be evenly spaced ideally 50mm in from the LadderLink edges to create a secure installation (see below diagram).

FIXING TO TIMBER PARAPET

- 1. Drill and install 4 (four) 14g x 75mm roofing screws (recommended to pilot drill holes).
- 2. Ensure the timber structure is secured in accordance with current Building Codes.

FIXING TO CONCRETE PARAPET

- 1. Drill and install 4 (four) M8 masonry bolts or equivalent anchor.
- 2. Ensure anchoring bolts are a minimum of 80mm from concrete wall edges.









▲ A FALL RESCUE PLAN SHOULD BE DEVELOPED PRIOR TO USING SAFETYLINK EQUIPMENT.

Figure 3 – Progressing along the line to point A.

THIS IS A GUIDE ONLY





PROGRESSING ALONG THE ANCHOR SYSTEM

THE FOLLOWING IS AN EXAMPLE OF PROGRESSING ALONG THE LINE TO POINT A IN FIGURE 3.

- 1. Consult site safety plan and plan your path accordingly. Do not attempt to bypass any consecutive anchors.
- 2. Find the safest access point around the perimeter of the building.
- 3. Check the access sign has a current certification.
- 4. Place a ladder on the fixed LadderLink and tie the ladder to LadderLink.
- 5. Inspect your full body harness gear and equipment as per manufacturers' instructions and fit to body as per manufacturers instruction fitting.
- 6. Connect Shock absorbing lanyard to metal D ring on the back of the harness via a karabiner.
- 7. Connect adjustable rope line to shock absorbing lanyard using a karabiner.
- 8. Connect the adjustable rope line to the first anchor. Do not attempt to step onto the roof unless this connection has been made and checked and any slack taken out of the line.
- 9. Dismount the ladder and connect the karabiner to second anchor.
- 10. Run adjustable rope line through karabiner and anchor (making sure to lock karabiner).
- 11. Continue connecting through anchors to reach desired location using same method as shown on figure 3 (figure 3 on previous page).

DISCONNECTING FROM THE ANCHOR SYSTEM

Complete job and work your way back to ladder disconnecting karabiners while back tracking back to ladder.

△ DURING INSTALLATION YOU MUST BE SAFE AT ALL TIMES.

Where a risk of a fall exists on entering or exiting the SafetyLink[™] system additional fall prevention measures must exist. Where additional fall prevention exists on entry and exit the user must ensure:

- 1. Attachment is correctly made to the life line system before detaching from the additional fall prevention system.
- 2. DO NOT detach from the lifeline system unless correct attachment is made to the additional fall prevention system.







SAFETYLINK ANCHORAGES


(In accordance with AS/NZS 1891.4:2009 clause 9.1)

ALL ANCHORAGES MUST BE INSPECTED EVERY 12 MONTHS, inspections need to be carried out by a competent height safety installer. The system also needs to be re-certified by an Engineer where the systems original date of installation exceeds 10 years, and every subsequent 5 years after that.

Procedures to be followed at inspection time:

- Visually inspect anchors for signs of deterioration.
- The FrogLink/TileLink anchor point has two energy absorbing regions and two stabilising joins which hold the eyelet in
 place during use. If these energy absorbing regions are expanded this will indicate the anchor point has arrested a fall.
 Similarly, if the two stabilising joins have been broken this would also indicate the FrogLink/TileLink has arrested a fall
 and should be replaced.
- The eyebolt should remain straight, a bent eyebolt will indicate that the anchor point has arrested a fall (*The design features of the eyebolt includes the ability to bend like a fishing pole starting from the top and working its way to the bottom, enabling it to use up energy as the eyebolt bends whilst lessening the force on the person falling and the attachment point).*
- Visually inspect the components of the anchor for corrosion, superficial surface marking is permitted while deeper corrosion or pitting would require attention.
- Manually (by hand) check the eyebolt for rigidity and tightness, if the eyebolt can turn in the anticlockwise direction it will require attention.
- Visually inspect the rubber hat washer and waterproofing components to ensure it has remained sealed.
- Visually inspect the attachment component of the anchorage where practically possible.
- Visually inspect the parent structure for modifications or deterioration which might lead to loss of anchorage strength.
- To comply with Australian Standards, each Concrete Anchor must be tested after installation and at every recertification inspection. Ensure you wait the recommended curing time as specified by the chemical anchor instructions. The pull test can be done using a 16mm threaded eyebolt. Test consists of ultimate pull out force proof loading to 50% of design purpose of anchorage.







ANCHORS AND LADDER STABILISERS INSTALLATION AND RECERTIFICATION CHECKLIST

This checklist is to help you compile information about the SafetyLink Anchor and Ladder Stabiliser Systems to ensure it is installed and maintained as per SafetyLink Installation Guides.

All anchorages and swaged/swageless/crimped components must be inspected every 12 months, inspections need to be carried out by a competent height safety equipment inspector who has been trained in the safe use and maintenance of this system. The system will require recertification by height safety assessor "suitable qualified engineer or competent height safety installer as defined in AS/NZS 1891.4:2009 clause 1.4 DEFINITIONS" where the systems original date of installation exceeds 10 years, and every subsequent 5 years after that.

All anchors must be numbered and tagged as compliant at installation and re-tagged on re-certification. Tag number codes are to be used in conjunction with a site plan.

NOTE: THIS CHECKLIST IS TO BE USED IN CONJUNCTION WITH A SITE LAYOUT PLAN AND SAFETYLINK INSTALLATION GUIDES AND USER MANUALS.

Date checklist completed://				
Date checklist to be redone (annually or when there is a change or addition to the system):///				
Name(s) of person(s) who completed checklist:				
Position: Company:				

OVERALL CHECK			ACTION TAKEN IF NO
Review site layout plan, have the anchors been correctly positioned?	□ Yes	🗌 No	
Have all anchors and components been tagged and noted on site plan?	□ Yes	🗌 No	
Have all anchors been installed as per SafetyLink Installation Guides?	🗌 Yes	□ No	

Visually inspect all Ladder Support Brackets for any signs of deterioration or the protective coating being removed.Image: Content of the cont	INDIVIDUAL ANCHOR AND COMPONENT CHECK	Insert number code for NON COMPLYING anchors or components (per site plan).	ACTION TAKEN to rectify non complying anchors.
structure as per SafetyLink Installation Handbook. Image: Contemportal SafetyLink Installation Handbook. Visually inspect the parent structure for modifications or deterioration which might lead to loss of anchorage strength. Image: Contemportal SafetyLink Installation Handbook. Visually inspect the Anchor for corrosion, superficial surface marking is permitted while deeper corrosion or pitting would require attention. Image: Contemportal SafetyLink Installation Handbook. Visually inspect the components of the anchor for corrosion, superficial surface marking is permitted while deeper corrosion or pitting would require attention. Image: Contemportal SafetyLink Installation Handbook. Visually inspect the components of the anchor for corrosion or pitting would require attention. Image: Contemportal SafetyLink Installation Handbook. Visually inspect the attachment component of the anchorage where practically possible. Image: Contemportal SafetyLink Installation Handbook. Check all Locking Hex Nuts on anchors are tightly secured. Image: Contemportal SafetyLink Installed and should be taken out of service. Manually check the Eyebolt for rigidity and tightness; if the eyebolt can turn in the anticlockwise direction it will require attention. Image: Context Installed and secured correctly. Installed onto Roof Sheet laps/joins. Check that ten (10) tri-fold rivets have been install the SurfaceLink Place. Check the rivets have been installed and secured correctly. Image: Context Installed and secured correctly. Installed onto Roof Sheet screwline. Check one	, , , , , , , ,		
deterioration which might lead to loss of anchorage strength.Visually inspect the Anchor for corrosion, superficial surface marking is permitted while deeper corrosion or pitting would require attention.Visually inspect the components of the anchor for corrosion, superficial surface marking is permitted while deeper corrosion or pitting would require attention.Visually inspect the attachment component of the anchorage where practically possible.Check all Locking Hex Nuts on anchors are tightly secured.The Eyebolt should remain straight, a bent eyebolt will indicate that the anchor point has arrested a fall and should be taken 			
marking is permitted while deeper corrosion or pitting would require attention.Visually inspect the components of the anchor for corrosion, superficial surface marking is permitted while deeper corrosion or pitting would require attention.Visually inspect the attachment component of the anchorage where practically possible.Check all Locking Hex Nuts on anchors are tightly secured.The Eyebolt should remain straight, a bent eyebolt will indicate that the anchor point has arrested a fall and should be taken out of service.Manually check the Eyebolt for rigidity and tightness; if the eyebolt can turn in the anticlockwise direction it will require attention.Installed onto Roof Sheet laps/joins. Check that ten (10) tri-fold rivets have been used to install the SurfaceLink Plate. Check the rivets have been installed and secured correctly.Installed onto Roof Sheet screwline. Check one roofing screw is			
superficial surface marking is permitted while deeper corrosion or pitting would require attention.Visually inspect the attachment component of the anchorage where practically possible.Check all Locking Hex Nuts on anchors are tightly secured.The Eyebolt should remain straight, a bent eyebolt will indicate that the anchor point has arrested a fall and should be taken out of service.Manually check the Eyebolt for rigidity and tightness; if the eyebolt can turn in the anticlockwise direction it will require attention.Installed onto Roof Sheet laps/joins. Check that ten (10) tri-fold rivets have been used to install the SurfaceLink Plate. Check the rivets have been installed and secured correctly.Installed onto Roof Sheet screwline. Check one roofing screw is	marking is permitted while deeper corrosion or pitting would		
where practically possible.Image: Check all Locking Hex Nuts on anchors are tightly secured.Check all Locking Hex Nuts on anchors are tightly secured.Image: Check all Locking Hex Nuts on anchors are tightly secured.The Eyebolt should remain straight, a bent eyebolt will indicate that the anchor point has arrested a fall and should be taken out of service.Image: Check all Check the Eyebolt for rigidity and tightness; if the eyebolt can turn in the anticlockwise direction it will require attention.Installed onto Roof Sheet laps/joins. Check that ten (10) tri-fold rivets have been used to install the SurfaceLink Plate. Check the rivets have been installed and secured correctly.Image: Check one roofing screw isInstalled onto Roof Sheet screwline. Check one roofing screw isImage: Check one roofing screw is	superficial surface marking is permitted while deeper corrosion		
The Eyebolt should remain straight, a bent eyebolt will indicate that the anchor point has arrested a fall and should be taken out of service.Image: Comparison of the eyebolt for rigidity and tightness; if the eyebolt can turn in the anticlockwise direction it will require attention.Image: Comparison of the eyebolt for rigidity and tightness; if the eyebolt can turn in the anticlockwise direction it will require attention.Image: Comparison of the eyebolt for rigidity and tightness; if the eyebolt can turn in the anticlockwise direction it will require attention.Image: Comparison of the eyebolt for rigidity and tightness; if the eyebolt can turn in the anticlockwise direction it will require attention.Image: Comparison of the eyebolt for rigidity and tightness; if the eyebolt can turn in the anticlockwise direction it will require attention.Image: Comparison of the eyebolt for rigidity and tightness; if the eyebolt can turn in the anticlockwise direction it will require attention.Image: Comparison of the eyebolt for rigidity and tightness; if the eyebolt can turn in the anticlockwise direction it will require attention.Image: Comparison of the eyebolt for rigidity and tightness; if the eyebolt can turn in the anticlockwise direction it will require attention.Image: Comparison of the eyebolt for rigidity and tightness; if the eyebolt can turn in the anticlockwise direction it will require attention.Image: Comparison of the eyebolt for rigidity and tightness; if the eyebolt can turn in the anticlockwise direction it will require attention.Image: Comparison of the eyebolt for rigidity and tightness; if the eyebolt can turn in the anticlockwise direction it will require attention.Image: Comparison of the eyebolt for rigidity and tightness for eyebolt for eyebolt for eyebolt for eyebolt for eyebolt fo			
that the anchor point has arrested a fall and should be taken out of service.Evebolt for rigidity and tightness; if the eyebolt can turn in the anticlockwise direction it will require attention.Evebolt for rigidity and tightness; if the eyebolt can turn in the anticlockwise direction it will require attention.Installed onto Roof Sheet laps/joins. Check that ten (10) tri-fold rivets have been used to install the SurfaceLink Plate. Check the rivets have been installed and secured correctly.EveloptionInstalled onto Roof Sheet screwline. Check one roofing screw isEveloption	Check all Locking Hex Nuts on anchors are tightly secured.		
eyebolt can turn in the anticlockwise direction it will require attention. Installed onto Roof Sheet laps/joins. Check that ten (10) tri-fold rivets have been used to install the SurfaceLink Plate. Check the rivets have been installed and secured correctly. Installed onto Roof Sheet screwline. Check one roofing screw is	that the anchor point has arrested a fall and should be taken		
rivets have been used to install the SurfaceLink Plate. Check the rivets have been installed and secured correctly. Installed onto Roof Sheet screwline. Check one roofing screw is	eyebolt can turn in the anticlockwise direction it will require		
-	rivets have been used to install the SurfaceLink Plate. Check the		
	-		





ANCHORS AND LADDER STABILISERS INSTALLATION AND RECERTIFICATION CHECKLIST

Insert number code for NON COMPLYING anchors or	ACTION TAKEN to rectify
components (per site plan).	non complying anchors.
	NON COMPLYING anchors or



9001 Quality

ANCHORS AND LADDER STABILISERS INSTALLATION AND RECERTIFICATION CHECKLIST

INDIVIDUAL ANCHOR AND COMPONENT CHECK	Insert number code for NON COMPLYING anchors or components (per site plan).	ACTION TAKEN to rectify non complying anchors.
S5_Z Clamps should be checked to ensure the setscrews are tensioned to 160 and 180 inch pounds on 22ga steel, and 130 to 150 inch pounds on all other metals and thinner gauges of steel (see installation guides).		
Ensure plate fixing bolts on the top of the S-5 Clamps are tightly secured.		
Ensure Retro Washers have additional silicone applied under the washer. Visually inspect the waterproofing component to ensure it has retained a weatherproof seal.		

▲ WARNINGS

During installation you must be safe at all times. All safety procedures must be complied with in accordance with the current legislation and regulations. Ensure safety at all times by being attached to anchor point approved safety equipment, using a scaffold or a secured ladder.

All items of equipment which are in regular use shall be subjected to periodic inspection and servicing. These regular scheduled inspections and servicing must be carried out by a competent height safety installer. *(refer to AS/NZS 1891.4:2009 if clarification required or contact us).*

The building or structure for the anchorages should be assessed by an engineer, unless it is clear to a competent height safety installer that the anchorages system is structurally adequate.

INSTALLATION MUST BE CARRIED OUT BY, OR UNDER THE SUPERVISION OF A COMPETENT HEIGHT SAFETY INSTALLER. If you are uncertain and need help please call +61 249 641068 or 1300 789545, email: info@safetylink.com or visit our website www.safetylink.com





10 YEAR RECERTIFICATION POLICY

10 years from the date of original installation SafetyLink Lifeline/Anchor Systems must be inspected by a suitably qualified engineer or competent height safety installer as defined in AS/NZS 1891.4:2009 clause 1.4 DEFINITIONS. The engineering level of inspection required must be carried out as follows:

Summary of requirements after 10 years from original installation date:

- a) The system is to be inspected to ensure it is installed as per SafetyLink's installation instructions.
- b) The system is to be inspected to ensure it passes the annual recertification criteria as set out in SafetyLink's *Installation and Recertification Checklist.*
- c) The structure is to be assessed for any modifications or deterioration which might lead to loss of anchorage strength, and either deemed safe for continued use or taken out of service.

Every 5 years after the 10 year Engineer recertification the SafetyLink Lifeline/Anchor Systems must be inspected by a suitably qualified engineer or competent height safety installer as defined in AS/NZS 1891.4:2009 clause 1.4 DEFINITIONS. The engineering level of inspection required must be carried out as follows:

Summary of requirements after 5 years from 10 year inspection date:

- a) The system is to be inspected to ensure it is installed as per SafetyLink's installation instructions.
- b) The system is to be inspected to ensure it passes the annual recertification criteria as set out in SafetyLink's *Installation and Recertification Checklist.*
- c) The structure is to be assessed for any modifications or deterioration which might lead to loss of anchorage strength, and either deemed safe for continued use or taken out of service.

▲ WARNINGS

During installation you must be safe at all times. All safety procedures must be complied with in accordance with the current legislation and regulations. Ensure safety at all times by being attached to anchor point approved safety equipment, using a scaffold or a secured ladder.

All items of equipment which are in regular use shall be subjected to periodic inspection and servicing. These regular scheduled inspections and servicing must be carried out by a competent height safety installer. (refer to AS/NZS 1891.4:2009 if clarification required or contact us).

The building or structure for the anchorages should be assessed by an engineer, unless it is clear to a competent height safety installer that the anchorages system is structurally adequate.


INSTALLATION MUST BE CARRIED OUT BY, OR UNDER THE SUPERVISION OF A COMPETENT HEIGHT SAFETY INSTALLER.

If you are uncertain and need help please call +61 249 641068 or 1300 789545, email: info@safetylink.com or visit our website www.safetylink.com





EXPERT FALL PROTECTION PLANNING



SafetyLink's design and planning team are here to help work out the positioning of your fall protection system, ensuring all areas of your roof are accessed safely.

Things to consider when planning your roof layout:

- Are all areas of your roof protected, allowing complete access when working at heights?
- Are you protected from the ground up, allowing complete access to your roof?
- Detailed comprehensive documentation provided e.g. installation guides, testing results, product sheets should be provided.
- SafetyLink can also provide you with a qualified and reputable installer of SafetyLink products.

Contact our design team at info@safetylink.com and we can plan your fall arrest system for you.





NOTES







▲ A FALL RESCUE PLAN AND SAFE WORK STATEMENT MUST BE DEVELOPED PRIOR TO USING SAFETYLINK SYSTEMS AND EQUIPMENT.

$\ensuremath{\vartriangle}$ PERSONS WORKING AT HEIGHTS SHOULD NOT WORK ALONE.

It is critical that before using any SafetyLink Systems a fall rescue plan is in place for any persons suspended mid-air following a fall. Serious injury or death can occur in a matter of minutes, particularly if a person's movement or breathing is restricted or loss of consciousness has occurred. In accordance with your fall rescue plan and appropriate first aid procedures it is essential to remove the person from the suspended position as quickly as possible.


IN ACCORDANCE WITH AS/NZS 1891.4:2009 CLAUSE 9.5

EQUIPMENT WHICH HAS ARRESTED A FALL OR SHOWS A DEFECT

Any piece of equipment including both personal and permanently installed items, which has been used to arrest a fall or which shows any defect during operator or periodic inspection shall be withdrawn from service immediately and a replacement obtained if necessary. A label indicating the condition or defect should be attached to the equipment, and it should be examined by a competent height safety installer who will decide whether the equipment is to be destroyed or repaired if necessary and returned to service. In the latter case, details of any repair shall be documented, and a copy given to the operator.



SafetyLink Pty Ltd | ABN 83 081 777 371 | www.safetylink.com



Asia-Pacific/The Americas | +61 2 4964 1068 | info@safetylink.com Europe/Africa/Middle East | europe.sales@safetylink.com Northern Europe | uk.sales@safetylink.com